From:	Bernhart, Michael R
To:	Bruce Zook
Subject:	RE: UV system- Control Program Improvements for Colorado Springs Utilities
Date:	Tuesday, May 15, 2018 11:37:19 AM

[External Email - Be careful! DO NOT open attachments or click links from unknown senders or unexpected email.]

Yes, I received it. I sent the request to those in the know and we are discussing. I think switching which modules can be lead will not be feasible since you have a stepped channel, the last module has a 5 inch step higher than the first module so that may cause dosing issues. Once I get a firm word I'll forward on to you.

Michael Bernhart
Manager, Field Services
Purification & Disinfection Systems
aquaray®, aquasource® & ozonia® products
Water Technologies & Solutions

Tel: 201.676.2567
Mob: 201.294.3994

SUEZ Treatment Solutions Inc.
600 Willow Tree Rd.
Leonia, NJ 07605
www.suezwatertechnologies.com
Twitter : @suezWATERTECH

From: Bruce Zook <bzook@csu.org>
Sent: Tuesday, May 15, 2018 1:32 PM
To: michael.bernhart@suez.com
Subject: RE: UV system- Control Program Improvements for Colorado Springs Utilities

I only wanted to confirm that you received this, nothing else. Thank you.

Make it a great day

Bruce Zook
Project Manager
Colorado Springs Utilities- Wastewater Treatment Department
(719) 668-8250 - office
(719) 896-6860 - cell

From: Bruce Zook
Sent: Friday, May 11, 2018 9:18 AM
To: 'michael.bernhart@suez.com' <michael.bernhart@suez.com>
Cc: Eric Lindgren <elindgren@csu.org>; Gary Marshall <gmarshall@csu.org>
Subject: UV system- Control Program Improvements for Colorado Springs Utilities

It was good to talk to you yesterday. I apologize for not getting this out yesterday but you know how things go sometimes.

To follow up with our conversation, above is the descriptive summary for our system. To summarize, here is what we would like to accomplish:

1. The ability to run any one of the 3 banks in a specific channel as the lead. We see several benefits to this:
    a. We can equalize run time on the power supplies to the banks. As it is now one bank is taking over 80% of the run load and the power supplies in the first two banks (3 banks per channel) are going to need to be replaced well ahead of their full use.
    b. We can equalize run times on the bulbs. Again one bank is being heavily used and we are getting good use from those bulbs. The second to come on will be replaced based on the # of strikes, not hours, and the third bank (first in the flow path) see almost no use. In order to move the bulbs it is a major event and challenging to track the bulb location in the existing program.
    c. Similar to a) and b) above the air conditioners on the power supply cabinets are also loaded very differently and the AC on the lead bank are failing at a much higher rate. It would make it much easier to operate if we could select one of the other banks to be the lead if it was operating more reliably. This would allow us to fix any operational issues without missing a beat. I am told now that this is a cumbersome manual activity.
2. We would like to be able to change the setting where a second unit comes on. I am told not that does not occur until the lead bank reaches 100%. Considering the heat load and the degradation of the AC units on the power supplies we would like to be able to set this ourselves. There are times that we would like to reduce this to 80% or maybe down as low as 70% based on run condition of the equipment. It seems like we should be allowed this operational flexibility.
3. Ability to download bulb run times and strikes from the control system. I am told that right now the only means we have to do this is by walking through the local control panels and writing down the values. This is a limitation in our asset management program.

I look forward to hearing back from you as to the potential improvements you can help us with on our control system. All of it is based on increasing reliability and getting maximum life out of the assets. We understand that some of this may mean that the system operates below its maximum efficiency but operation cost is not dependent solely on the cost of power fed to the unit.

I look forward to your response.

Make it a great day

Bruce Zook
Project Manager
Colorado Springs Utilities- Wastewater Treatment Department
(719) 668-8250 - office
(719) 896-6860 - cell

CONFIDENTIALITY NOTICE - This email transmission, and any documents, files or previous email messages attached to it, may contain information that is legally privileged or otherwise confidential to include customer and business information. If you are not the intended recipient, or an authorized person for the intended recipient, you are hereby notified that any disclosure, copying or distribution of this information, or any action taken in reliance on the information contained within this email, is strictly prohibited. If you have received this email message in error, please notify the sender and then delete the message (and any attachments) from your computer and/or network. Thank you.